Embankment Reinforcement

PFA Rising Lane, Enkagrid Pro, A50 Growth Corridor, Uttoxeter, UK






Project Description

The 1.5km A50 Growth Corridor road development project to the West of Uttoxeter provides improved access to new housing and employment sites and is part of a multi-million pound investment by Government under the control of Staffordshire County Council. It also improves the access to the existing and new JCB factories to the north of the A50. The scheme delivered a gradeseparated junction where embankments have been raised to an overbridge of the A50.

The Challenge

Site investigation in the area where the embankments were raised showed patches of soft made ground susceptible to differential settlement. The specification gave the option to the contractor to use a locally supplied light weight Pulverised Fly Ash (PFA) to reduce overall settlement. The challenge was to reduce the differential settlement and to give stability to the 1 in 2 rising side slopes which curved around a SuDS balancing pond. The nature of PFA is that it is fine grained and often of a high acidity. Any material used should be able to withstand any corrosive effects of the PFA, bond with the PFA and be easy to cut to shape around the relatively tight curve of the embankment. A low-creep, high-stiffness material would be preferred as any movement in the PFA is detrimental to the compaction process. As Highways England manages the A50 trunk road, BBA certification was required.

Client	Staffordshire County Council / Highways England
Contractor	Tarmac
Products	ABG Enkagrid Pro
Quantity	65,000m²
Benefits	 Maximum compaction and reinforcement of PFA Steeper slopes using PFA Instant load transfer – no movement



ABG Enkagrid Pro

Embankment Reinforcement

PFA Rising Lane, Enkagrid Pro, A50 Growth Corridor, Uttoxeter, UK





The Solution


ABG Enkagrid Pro was selected as a highly stable BBA certified low-creep geogrid. The stiffer grid lays flat and presents a high friction surface to the finely graded PFA enabling good load spreading. The grid is cut to shape easily using a disc cutter on site to suit the curved embankment. The rolls of grid are placed using a spreader beam and then overfilled allowing compaction equipment to pass over the edge of the grid (1.), ensuring a fully compacted surface. The face is then trimmed back to line (2.) and finally sealed with a clay fill and finished with a layer of topsoil (3.).

The ABG Service


ABG supplied Tarmac with all the relevant certificates and technical data sheets to satisfy the requirements of the consultant to BS8006 - Code of Practice for Strengthened/ Reinforced Soils and Other as well as cortication required by Highways England via BBA.




Early retention of soil and seeds encouraging early germination



1. Install grid and overfill horizontally by 500mm and compact over the end of the arid



2. Cut the loose soil back to the compacted front face in line with the grid



3. Place selected clay to seal PFA and topsoil slope

Preparation of the slope ensuring maximum compaction and reinforcement of the PFA



Composite root structure supporting healthy and sustainable vegetation